BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

Tender No: BBMP/EE/DD/TEN/05/12-13 Date: 29.09.2012 Item No: 21

NEGOTIATED SCHDULE-B

NAME OF WORK: Providing Cement Concrete to Cross Roads at Mantapa Pradesh area, in Ward No. 13, in Shettyhalli Sub-Division

Sl. No	Description of work	Unit	Qty	Rates Quoted by Contractor	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Earthwork in surface excavation in ordinary soil for levelling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift up to 1.5m, excavated surface leveled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed complete as per specifications.	Cum	25.92	125.00	Rupees One Hundred Twenty Five Only
2	Earthwork excavation for foundation of buildings, culverts, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead up to 50 m. after breaking of clods complete as per specifications.	Cum	282.80	149.00	Rupees One Hundred Forty Nine Only
3	Providing Granite slabs selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc. complete as per specifications.	Sqm	180.00	337.00	Rupees Three Hundred Thirty Seven Only
4	Providing and laying in position plain cement concrete of nominal mix M 10 with OPC cement @ 220kgs, with 40mm and down size graded granite metal machine mixed, concrete laid in layers not exceeding 15cms thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	89.49	4280.00	Rupees Four Thousand Two Hundred Eighty Only
5	Providing and constructing granite / trap / basalt rubble stone masonry in foundation with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.	Cum	12.96	3391.00	Rupees Three Thousand Three Hundred Ninety One Only

Signature of the Contractor

Executive Engineer

6	Providing and laying cement concrete using 20mm and down size granite jelly of ready mixed concrete (RMC)for R.C.C works laid in 15cms thick layers and well compacted vibrating, curing, finishing with necessary cement mortar, form works and scaffoldings to withstand pumping of concrete, with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges.) Ready mixed Cement concrete M-20 (1:1.5:3) for raft foundation, column footing, main and secondary beams.	Cum	92.66	4896.00	Rupees Four Thousand Eight Hundred Ninety Six Only
7	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.	Qtls	3.73	7569.00	Rupees Seven Thousand Five Hundred Sixty Nine Only
8	Providing & fixing 20 mm thick compressible fibre board in expansion joint complete as per Drawing & Technical Specification. Complete as per Specifications.	m	72.00	138.00	Rupees One Hundred Thirty Eight Only
9	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 10 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading	Cum	298.00	79.00	Rupees Seventy Nine Only

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,